No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs.
	SLUICE AT R.L. 46·00.				
1	Earthwork excavation cutting open bund ...	C.yd.	0 2 6	130	
2	Do do for foundation ..	,,	0 2 6	6	
3	Concrete stone jelly in surki mortar ..	C.ft.	0 4 0	138	
4	Burnt brick in surki mortar	,,	0 4 0	322	
5	Burnt stone slab 6″ thick dressed and fixed ..	S.ft.	0 5 0	146	
6	Cutting holes in orifice slabs, etc.	Each	0 8 0	4	
7	Plastering with surki mortar	Sqr.	3 0 0	3·27	
8	Providing and fixing a new plug and rod with locking arrangements	Each	15 0 0	1	
9	Refilling the cut opened portion with earthwork including consolidation and watering.	C.yd.	0 2 6	130	
10	Providing and fixing C.I. pipe 6″ dia. and including carting and fixing, etc., complete	R.ft.	3 0 0	48	
11	Cut opening bund, dismantling the existing sluice and refilling the cut opened portion with earthwork and consolidation.	L.S.	..	..	
	Total ..				
	Constructing another sluice same as above ..				
	Total ..				
	WASTE WEIR AT R. L. 53.00.				
1	Benching rock for foundation	S.ft.	0 6 0	715	
2	Size stone in surki mortar with necessary bond stones	C.ft.	0 4 6	3,055	
3	Size stone in cement mortar (1 : 3) ..	,,	0 8 0	213	
4	Cement mortar pointing after racking joints	Sqr.	3 8 0	25.40	
5	Burnt stone slabs 6″ thick dressed and fixed ..	S.ft.	0 5 0	46	
6	Rough stone work new with jelly wedging ..	C.yd.	1 8 0	15	
	Total ..				

C. R. IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 10th May 1940.

The attention of the public is invited to the detailed notification, dated 5th May 1940, published on pages 1089-1091, Part VI of the *Mysore Gazette*, dated 16th May 1940, regarding tenders for constructing a High Level Causeway across the Gundlu River along Kabbahalli Road from 3/117 of Bangalore-Nilgiri Road, Gundlupet Taluk.

The last date for lodging of tender is 1st June 1940 up to 12 NOON.

S. RAMASWAMY,
Executive Engineer.